

: TASKING :

16' X 26' HOUSE

Rg 36-27
Vol 20
File 700
Tasking

15	Cedar Block			Foundations	@ .10	1.50
3	pcs. 4 X 4	26 ft.		Sills	104 B. M.	
14	" 2 X 4	16 ft.		Joists	150 B. M.	
6	" 2 X 3	26 ft.		Plates	78 B. M.	
12	" 2 X 3	16 ft.		Plates	96 B. M.	
18	" 2 X 3	16 ft.	Ceiling Joists	64 B. M.		
42	" 2 X 3	8 ft.	Studs	168 B. M.		
15	" 2 X 3	3 ft.	Headers	22 B. M.		
20	" 2 X 3	10 ft.	Rafters	100 B. M.		
					782 B. M. ft. @25.00	19.55

SHIPLAP

Floor		416 B. M.				
Walls		672 B. M.				
Roof		560 B. M.				
Partition		384 B. M.				
Ceiling		416 B. M.	2448	@ 25.00		61.20
				@ .75		8.75
5	Sash			@ 4.00		4.00
1	Door					.25
1	Pr. Butts					.30
1	Thumb Latch					.40
8 1/2	Rolle Wartime Roofing			@ 2.40		20.40
1/3	" Sulphite Paper			@ 4.90		1.63
1	Roof Jack					3.00
Nails						23.75
Labour		95 Hours		@ .25		
						145.08
TOTAL COST						